

ADDENDUM #2

Colley Drive Special Assessment
Project No. SA-105
Bid No. 15-0007

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

The following questions were asked via email.

Questions and Answers:

Q1. What is the next option if the existing soil cement base cannot be mixed with a road reclaimer?

A1. The contractor shall reclaim and mix the existing base and subbase as needed to achieve the required depth per the approved plans.

Q2. Is silt fence required on both side of the R.O.W?

A2. The contractor shall install silt fence along the R/W limits of the project on both sides of the road. Additionally, the contractor shall maintain proper BMP's for erosion control throughout the duration of the project. Please see sheets 4 & 5 of the approved construction plans for details related to erosion and sediment control.

Q3. Is there any existing underground utilities?

A3. The City of Tavares has indicated they do not have facilities within the project limits. All other utilities appear to be aerial; however, it is the Contractor's responsibility to verify utility location. Please see sheet 4 of the approved construction plans regarding Utilities.



Terry Scott, Construction Inspection Supervisor